

STATE OF MICHIGAN DEPARTMENT OF ENVIRONMENT, GREAT LAKES, AND ENERGY

LANSING DISTRICT OFFICE



April 25, 2022

Troy Bell
City of Muskegon Heights
2724 Peck Street
Muskegon Heights, Michigan 49444

WSSN: 04580 County: Muskegon

Dear Troy Bell:

SUBJECT: City of Muskegon Heights (City)

2022 Water System Sanitary Survey (Survey)

This letter confirms the Department of Environment, Great Lakes, and Energy's (EGLE) staff meetings with John Allen on March 14 and 30, 2022, to conduct a Survey of the City's water system, and to present the final findings, discuss areas for improvement, and identify timelines for corrective action where appropriate. The purpose of a Survey is to evaluate the water supply system with respect to the requirements of the Michigan Safe Drinking Water Act, 1976 PA 399, as amended (Act 399). It is also an opportunity to update EGLE's records, provide technical assistance, and identify potential risks that may adversely affect drinking water quality. Enclosed, is a copy of the Sanitary Survey Report for your reference.

Since the last Survey, EGLE acknowledges and appreciates that the City has completed the following water system improvements:

- 1. Fixed drainage issues near the flocculation and sedimentation basins that were identified in previous Surveys.
- Completed meter replacement project and verified service material entering all homes.
- 3. Initiated a lead service line replacement and materials inventory program.
- Received a drinking water revolving fund (DWRF) loan for lead service line replacement (LSLR), watermain replacement, and transmission main upgrade projects.
- 5. Completed a rate increase to allow for acceptance of the DWRF loan.

The following table summarizes EGLE's final findings from the Survey of the water system:

Survey Element	Findings		
Source	Recommendations Made		
Treatment	Recommendations Made		
Distribution System	Deficiency Identified		
Finished Water Storage	Deficiencies Identified		
Pumps	Recommendations Made		
Monitoring & Reporting	Deficiencies Identified		
Management & Operations	Deficiencies Identified		
Operator Compliance	Required Actions Identified		
Security	Deficiency Identified		
Financial	Deficiency Identified		
Other	No deficiencies/recommendations		

<u>Deficiencies</u>:

Deficiencies indicate non-compliance with one or more Act 399 requirements, which include defects in a water system's infrastructure, design, operation, maintenance, or management that cause, or may cause, interruptions to the "multiple barrier" protection system and adversely affect the system's ability to produce safe and reliable drinking water in adequate quantities.

During the Survey, eight deficiencies were identified and are listed below:

- 1. R 325.11905 requires the City to have an operator in charge (OIC) of the distribution system with at least an S-2 license. Per EGLE's operations oversight policy, the OIC must visit staff daily, be on call 24/7, and supervise and direct staff responsible for daily operations. The full-time distribution OIC left City employment last year and the position is currently being filled part time by John Allen, who oversees daily operations at the water treatment plant (WTP) in addition to other duties. Currently, the City is not meeting the distribution system oversight requirements. The City needs to evaluate options for meeting this requirement, such as a full-time distribution OIC, contract operator, etc. Please indicate how the City will satisfy this requirement in the Survey response letter and submit an operator designation form to EGLE for our records.
- 2. R 325.10720 requires the monitoring of turbidity and the proper calibration of turbidimeters. United States Environmental Protection Agency (U.S. EPA) guidance dictates that turbidimeters must be calibrated (or must have the calibration verified) at least quarterly using an approved procedure. The City's current calibration procedure for online turbidimeters uses a calibration kit with a small glass cuvette inserted. This does not meet EGLE requirements. Quarterly calibrations or verifications must be completed under identical optical conditions as when the instrument is in operation. Additionally, the City could not produce

2022 records of quarterly calibrations for the benchtop or online turbidimeters. The City must begin using an approved procedure for online turbidimeter calibration or verification that involves filling the instrument body with primary standard and start maintaining all calibration records by *May 31, 2022*.

- 3. R 325.10720(3) requires continuous monitoring for residual disinfectant at an entry point to the distribution system (EPTDS) on a continual basis and requires the daily minimum to be recorded. EGLE was informed during the Survey call on March 14, 2022, that the chlorine analyzer at the City's EPTDS had been offline since January 2022. EGLE staff confirmed the chlorine analyzer was operational during an in-person inspection on March 30, 2022. However, there is still a communication issue between the chlorine analyzer and the SCADA system, resulting in the SCADA system reporting inaccurately scaled values. The City must ensure the SCADA system is reporting the true measured chlorine residual by May 31, 2022. In addition, a standard operating procedure (SOP) for maintenance and verification of the instrument must be developed and implemented.
- 4. R 325.11112(c) states storage tanks shall have no unprotected openings. Per Ten States Standards, 7.0.7, overflows shall be fitted with twenty-four non-corrodible mesh screens, discharge 12 to 24 inches above the ground surface, and not be directly connected to any drain, sanitary sewer, or storm sewer. Overflow pipes are required to terminate above ground to prevent a cross connection, allow for observance of an overflow event, and more easily confirm there is not an obstruction in the overflow piping. Per 7.0.9, tank vents shall be fitted with twenty-four non-corrodible mesh screens and elevated tank vents shall open downward. During the Survey, the following items were observed:
 - a. The WTP reservoir overflows consist of a weir that is piped underground to a sewer manhole that then discharges to the on-site lagoon. Size 24 mesh must be installed on the overflow discharge and the pipe between the weir and manhole must be verified to be free flowing on a regular schedule through a method proposed by the City.
 - b. The Sherman reservoir had undersized vent screens. The Sherman reservoir overflow consists of a weir that flows to a pipe underground and discharges into a chamber that feeds a sanitary sewer. The overflow pipe had a flapper valve that was observed to be partially open and missing a screen. Size 24 mesh must be installed on the vents and overflow pipe. The flapper valve must be flush with the overflow pipe to prevent animals from entering the reservoir and the condition of the valve position verified periodically. Additionally, please propose a method for the reservoir overflow to conform with section 7.0.7 of Ten States Standards.
 - c. The Getty elevated tank rooftop wet interior access hatch is extended with approximately 20 inches of coarse mesh wall, which can allow rain and contaminants to enter the tank. The extended mesh venting on the wet

interior access hatch must be removed and replaced with an overlapping lid and watertight gasket. Additionally, the status of the overflow flapper valve and screen must be confirmed, and any needed correction made.

Please submit a corrective action plan and schedule with the Survey response letter to address these findings.

8. R 325.12303 states that emergency response plans (ERP) at a minimum, shall outline a program for rapid correction or mitigation of emergencies. The current ERP consists of a list of outdated contacts and does not include any SOPs for correction or mitigation of any emergencies, such as watermain breaks or source water contamination. The City must update their ERP to include all elements as outlined in Rule 2303 by July 31, 2022. Enclosed is a template for your use.

As a reminder, the U.S. EPA required the City to complete a Risk and Resiliency Assessment (RRA) and an ERP update as part of the 2018 America's Water Infrastructure Act (AWIA) requirements. Certification that both items are complete must be submitted to the U.S. EPA. The RRA certification was due on June 30, 2021, and the ERP certification was due on December 31, 2021. Contact the U.S. EPA at dwresilience@epa.gov for more information on AWIA requirements.

- 6. R 325.11403 prohibits cross connections for all customer classes, including residential customers. The City has implemented a commercial cross connection control program and performs opportunistic inspections of residential customers when access is granted to the residence. Implementation of this program must be expanded to all residential customers to provide a complete inventory of cross connection devices. The City must submit an implementation plan by June 30, 2022, for a fully expanded residential cross connection control and inspection program. The City must submit updates to cross connection program efforts by March 31, 2023, and March 31, 2024, which may be submitted as part of the cross connection annual report to help evaluate progress toward resolving this deficiency.
- A. R 325.11203 states that a water supply shall conduct a reliability study (Study) to determine the quantity of water needed for the waterworks system and shall update the Study every five years unless a waiver is requested and approved by EGLE. The City's last Study was completed in 2015 and is due for an update. Please submit an updated Study by October 31, 2022. If the City plans to pursue a waiver, please provide a written request with water demand data to support the request.
- 8. R 325.11606 outlines the required components of Asset Management Programs (AMP): inventory of assets, methods used to determine the asset criticality and consequence of failure, level of service goals, a capital improvements plan (CIP) that identifies system needs for 5 and 20-year planning periods, and an explanation of the funding structure and rate methodology that provides sufficient

resources to implement the AMP program. EGLE reviewed the City's AMP, received on February 28, 2018, and found the AMP did not meet requirements or provide an explanation of the funding structure. EGLE also reviewed water system budgets and the 7-year CIP to assess the City's financial capacity. EGLE observed that the CIP and budget do not include all water system needs, such as replacement of undersized watermain and lead service lines.

To return to compliance, the City must complete an AMP that is reflective of water system needs and include a comprehensive rate study in the rate methodology section. It is EGLE's understanding that the updated AMP will be completed with grant funds. *Please provide an updated AMP by October 31, 2022.*

Required Actions.

During the Survey, the following required actions were identified:

- The City has a complex water treatment and distribution system with aging infrastructure requiring qualified oversight. During the Survey, it was discussed that two out of three plant operators are expected to retire on January 1, 2023, and the certified OIC, the utilities director, may retire in the coming years as well. The distribution system has historically been understaffed and the full-time distribution OIC left City employment last year. Due to the loss of experienced water system staff, EGLE is concerned the City may not possess the managerial or technical capacity to oversee water system operations. Therefore, the City must submit a staffing plan that includes an evaluation of staffing needs, organizational chart, and efforts to recruit and retain operators with higher licenses by August 31, 2022. In addition to supporting staff training and licensure, written SOPs can ease future transition of leadership. SOPs must be developed for the following areas by December 31, 2022:
 - a. Pump Maintenance.
 - b. Sherman Street pump operation.
 - c. Storage management and high service pump station rotation.
 - d. Intake maintenance including backwash.
 - e. Chemical pump calibration.
 - f. Turbidimeter calibration.
 - g. Emergency power operation.
 - h. Interconnect use.
 - i. Chemical delivery procedure.
 - j. Bypassing storage tanks.
- 2. The Concentration of Chlorine x Time of Contact (CT) must be calculated daily and reported on the Monthly Operation Report (MOR), effective August 10, 2022. Reporting daily CT on the MOR allows EGLE staff to verify CT requirements are met and is used as a tool to ensure operators are aware of proper disinfection. The City reports the residence time in the flocculation basins, sedimentation

- basins, and the WTP reservoirs on the MOR, but does not account for short circuiting or complete a daily CT calculation. A summary of EGLE's CT calculation and example CT calculator will be provided to the City for reference.
- R 325.10604f(6) requires full replacement of lead service lines (LSLs) and galvanized services if the service line is or was connected to lead piping. Please continue to pursue replacement of all LSLs. Additionally, R 325.11604(c)(vii) requires the City to provide an annual report on LSLR efforts. The report for the 2021 calendar year is due *April 30*, 2022.
- R 325.11604(c)(ii) requires a complete distribution system materials inventory to be submitted to EGLE by *January 1, 2025*. Please ensure that ongoing verification efforts are sufficient to meet this deadline.
- 5. Isolation valves in the distribution system are necessary to minimize interruptions in service and sanitary hazards during construction or repairs, per R 325.11108. The City has a valve turning program that should result in the turning of each valve every five years. However, due to staffing limitations, there has been insufficient progress in the valve turning program in recent years, and the program hasn't been updated in several years. The valve turning program must be implemented. Please provide a program implementation plan by June 30, 2022, and an update on valve exercising activities by December 31, 2022.

Recommendations:

Recommendations are suggestions the public water supply should consider, to enhance its operations and services, and to avoid future deficiencies.

During the Survey, the following recommendations were identified, additional recommendations are included in an enclosure:

- Per Ten States 5.1.11(c) day tanks should hold no more than a 30-hour supply based on average demand. Based on this, the current day tanks for alum, chlorine, and fluoride are oversized, and should be resized accordingly.
- Begin routinely using the Area Wide Optimization Program (AWOP) worksheet to evaluate pretreatment and individual filter performance. Daily maximum raw, settled, individual filter effluent, and filter confluence turbidity data is needed for the AWOP worksheet. Consider submitting the AWOP worksheet monthly to EGLE or include the maximum individual filter effluent turbidity on the MOR.
- Budget for and replace undersized 4-inch and cast iron watermain that is beyond
 its useful life to increase the reliability and hydraulic capacity of the water system.
 Additionally, continue to address lost water concerns by replacing service lines
 with leaks.

- 4. Encourage all operators to obtain F-1 or S-2 licenses to increase redundancy in licensing and ensure proper succession planning.
- 5. Remove trees and vegetation from the Sherman reservoir hatches and vents to prevent bugs and other debris from entering the reservoir, as well as to keep tree roots from causing an issue with the tank structure or hatches. The Sherman reservoir is also overdue for a third-party inspection, which should be completed soon considering the age of the reservoir.
- 6. Develop standard specifications for watermain construction projects and submit them to EGLE for review.
- 7. EGLE encourages the City to complete annual inspections of the tank rooftop components. Establishment of a third-party maintenance contract could reduce this workload for City staff. Additionally, the City should budget to paint the elevated tank interior and exterior as indicated by third party inspection reports.

Please contact this office within 30 days of the date of this letter to acknowledge its receipt and respond to the recommendations and comments provided.

We anticipate and appreciate your cooperation in addressing these findings. If you have any questions, please feel free to contact me at 517-262-6795, or by e-mail at BatesC7@Michigan.gov.

Sincerely,

Summer Hought

Surface Water Engineer

Field Operations Section

Environmental Health Division

Summer Haught

Drinking Water and

517-899-4962

Caitlin Boths

Caitlin Bates, P.E.
Surface Water Treatment Specialist
Field Operations Section
Drinking Water and
Environmental Health Division
517-262-6795

Enclosures

cc/enc: John Allen, City

cc: Muskegon County Health Department

Michael Bolf, P.E., EGLE Ernie Sarkipato, P.E., EGLE

Sanitary Survey of Community Water Supply - Review Summary

Water Supply: City of Muskegon Heights

County: Muskegon Evaluator: Bates/Haught WSSN: 4580 District: 93

Construction & Maintenance Standby Power Isolation Source Water Protection Capacity Treatment Disinfection Fluoride Phosphate Addition Softening Iron/Manganese Removal Arsenic Removal Pretreatment Filtration (gravity or membranes) C*T Other Distribution System Interconnections w/ Other WS Hydrants & Valves Service Lines & Metering General Plan Cross Connections Construction & Maintenance Capacity Finished Water Storage	Update SWIPP	X	NotEv NoD/	X	Det	SigDe
Standby Power Isolation Source Water Protection Capacity Treatment Disinfection Fluoride Phosphate Addition Softening Iron/Manganese Removal Arsenic Removal Pretreatment Filtration (gravity or membranes) C*T Other Distribution System Interconnections w/ Other WS Hydrants & Valves Service Lines & Metering General Plan Cross Connections Construction & Maintenance Capacity			X X X	x		
Capacity Treatment Disinfection Fluoride Phosphate Addition Softening Iron/Manganese Removal Arsenic Removal Pretreatment Filtration (gravity or membranes) C*T Other Distribution System Interconnections w/ Other WS Hydrants & Valves Service Lines & Metering General Plan Cross Connections Construction & Maintenance Capacity			х			
Treatment Disinfection Fluoride Phosphate Addition Softening Iron/Manganese Removal Arsenic Removal Pretreatment Filtration (gravity or membranes) C*T Other Distribution System Interconnections w/ Other WS Hydrants & Valves Service Lines & Metering General Plan Cross Connections Construction & Maintenance Capacity			х	X		1
Disinfection Fluoride Phosphate Addition Softening Iron/Manganese Removal Arsenic Removal Pretreatment Filtration (gravity or membranes) C*T Other Distribution System Interconnections w/ Other WS Hydrants & Valves Service Lines & Metering General Plan Cross Connections Construction & Maintenance Capacity				X		1
Fluoride Phosphate Addition Softening Iron/Manganese Removal Arsenic Removal Pretreatment Filtration (gravity or membranes) C*T Other Distribution System Interconnections w/ Other WS Hydrants & Valves Service Lines & Metering General Plan Cross Connections Construction & Maintenance Capacity						MONES!
Phosphate Addition Softening Iron/Manganese Removal Arsenic Removal Pretreatment Filtration (gravity or membranes) C*T Other Distribution System Interconnections w/ Other WS Hydrants & Valves Service Lines & Metering General Plan Cross Connections Construction & Maintenance Capacity			ΙV	1 /		-
Softening Iron/Manganese Removal Arsenic Removal Pretreatment Filtration (gravity or membranes) C*T Other Distribution System Interconnections w/ Other WS Hydrants & Valves Service Lines & Metering General Plan Cross Connections Construction & Maintenance Capacity						
Iron/Manganese Removal Arsenic Removal Pretreatment Filtration (gravity or membranes) C*T Other Distribution System Interconnections w/ Other WS Hydrants & Valves Service Lines & Metering General Plan Cross Connections Construction & Maintenance Capacity		l x l				1
Arsenic Removal Pretreatment Filtration (gravity or membranes) C*T Other Distribution System Interconnections w/ Other WS Hydrants & Valves Service Lines & Metering General Plan Cross Connections Construction & Maintenance Capacity		12				
Pretreatment Filtration (gravity or membranes) C*T Other Distribution System Interconnections w/ Other WS Hydrants & Valves Service Lines & Metering General Plan Cross Connections Construction & Maintenance Capacity		X				
Filtration (gravity or membranes) C*T Other Distribution System Interconnections w/ Other WS Hydrants & Valves Service Lines & Metering General Plan Cross Connections Construction & Maintenance Capacity		X				
C*T Other Distribution System Interconnections w/ Other WS Hydrants & Valves Service Lines & Metering General Plan Cross Connections Construction & Maintenance Capacity			l I x			ľ.
Other Distribution System Interconnections w/ Other WS Hydrants & Valves Service Lines & Metering General Plan Cross Connections Construction & Maintenance Capacity	Conduct fitler studies every 5 years			l x l		ľ
Distribution System Interconnections w/ Other WS Hydrants & Valves Service Lines & Metering General Plan Cross Connections Construction & Maintenance Capacity	Report daily CT achieved on MOR		l x			ĺ
Interconnections w/ Other WS Hydrants & Valves Service Lines & Metering General Plan Cross Connections Construction & Maintenance Capacity	Evaluate day tank sizing			l x l		l
Hydrants & Valves Service Lines & Metering General Plan Cross Connections Construction & Maintenance Capacity					X	
Service Lines & Metering General Plan Cross Connections Construction & Maintenance Capacity	Develop SOP for use			X	1000	PROPERTY NAMED IN
General Plan Cross Connections Construction & Maintenance Capacity	Exercise all valves on a routine basis			l x l		ĺ
Cross Connections Construction & Maintenance Capacity	Continue verification efforts, LSL replacements		l x	^		i
Construction & Maintenance Capacity			l î	1		
Capacity	Develop residential program		^		x	
	Develop standard specs			X	^	
Finished Water Storage	Replace undersized 4 inch and cast iron watermain		1	x	A	
manda tratal diorago				1-	X	
Construction & Maintenance	Ensure tanks meet Ten State Standards	-2.3	MILES STATE OF THE PARTY OF THE	RESERVE OF		
Controls	The state of the s				X	
Capacity			X	1 1		
Pumps (All Pumping Facilities)			X	1		
Construction & Maintenance	Conduct periodic third party inspection			X		
Controls	Table periodic uma party mopodion	- 1		×		
Capacity			X			
Monitoring & Reporting			X			
Bacteriological Monitoring				1	X	Per La
Chemical Monitoring			X			
MOR or Annual Pumpage Report	Consider reporting AWOP data on MOR		X	1		
Consumer Confidence Report	Gondadi Topolang AWOT data Off WOR		1	X	1	
Analytical Capabilities	Turbidimeter calibrations/verifications, online CI analyzer		X	1 1		
System Management & Operations	Translatine Cambrations verifications, online Cl analyzer				Х	
Owner Responsibility				1	X	1-1-1
Capacity Development			X	1 1		
Reliability Study	Update study or request waiver		X	1 1		
Operations Oversight		.			X	
Permits	Comply with distribution operations oversight requiremen	ts		1 1	X	
Operator Compliance			X	\perp		
Operator Certification			X			
Technical Knowledge & Training	Develop stoffing plant & SOR-		X	1		
Security Security	Develop staffing plan & SOPs		X			
Emergency Response Plan	Undete FDD			199	X	
	Update ERP, conduct RRA				X	
Site Security (Fences, Alarms)			_ X	1 1		
Financial			^	1 1		
Rates			X		X	
Budget & Capital Imp. Plan			X		Х	
Other N/A - Not Applicable	Update AMP, conduct rate study		19 - 1 19 - 1 1 1 1 1 1 1 1 1 1 1 1 1 1			2 119
Rec - Recommendations Made			19 - 1 19 - 1 1 1 1 1 1 1 1 1 1 1 1 1 1		x	

SigDef - Significant Deficiencies Identified

	Additional Recommendations:
1	Update and submit the Source Water Intake Protection Plan to EGLE for approval.
2	Conduct comprehensive filter studies every five years. The study should include measuring media depth, core sampling, and sieve analysis, as well as verifying the filter backwash expansion rates.
3	Continue to ensure operators observe all filter backwashes.
4	Routinely calibrate chemical feeders.
5	Ensure turbidimeter controller settings match U.S. EPA recommended settings.
6	Ensure that all W I P valves are exercised on a routine basis
7	Conduct routine WTP generator load testing quarterly, and increase staff redundancy in knowledge of back up power transfer procedures.
8	Conduct periodic third party inspections of pumps.
9	Continue routine ground storage and elevated tank inspections by a third party.
10	Update the Revised Total Coliform Rule Sample Siting Plan and submit to EGLE for approval.
11	Consider development of an electronic work order system to track maintenance.
12	Develop a formal SOP for use of interconnects with the city of Muskegon and city of Norton Shores.
13	In order to receive CT credit in the filters, conduct a tracer test of the filters in accordance with Appendix C of the U.S. EPA's 1991 Surface Water Treatment Rules guidance manual.
14	Discourage hydrant tampering by enforcing the water use ordinance and consider installing tamper proof locks on vulnerable hydrants.

Alt. State No. (WSSN): 04580 Local Name (District): DISTRICT 93 Principle County: MUSKEGON

Billable Population: 10856 Service Connections: 5124

Activity Status: A

Activity Date: 1/1/1800 Op Category: F1 S2

% SW: 100 % **SWP**: 0

% GW: 0 % GWP: 0 % GWUI: 0

% GWUIP: 0

Owner Type: L

Primary Source: SW

Last Sanitary Survey: 3/30/2022

Popu	dation Hist	ory		Water System Flow Rates		DE VALS	Regulating Agency
Туре	Pop Count	Begin Date	End Date	Flow Rate Type	Quantity	/ Units	DISTRICT 93
R	10856	5/12/2015		BSLN Baseline Capacity	33.9	MGD	DISTRICT 9
R	11569	1/7/2011	5/12/2015				MDEQ
R	11741	2/1/2008	1/6/2011				
R	12049	10/17/2003	1/31/2008				
R	13000	8/12/2002	10/16/2003				
R	14611	1/1/1800	8/11/2002				

Points of Contact

PL

2724 PECK STREET

2724 PECK ST

MUSKEGON HEIGHTS, MI 49444

MUSKEGON HEIGHTS, MI 49444

MUSKEGON HEIGHTS, MI 49444

jallen@muskegonheights.us

DO Mr. JOHN C. ALLEN

CITY OF MUSKEGON HEIGHTS

DIR OF PUBLIC UTIL

231-780-3415 x 1

BUS FAX 231-780-2381 x

MOB

231-955-0050 x

FC Mr. TROY BELL

MUSKEGON HEIGHTS

CITY MANAGER

BUS 231-733-8870 x

AC Mr. TROY BELL

MUSKEGON HEIGHTS

CITY MANAGER

BUS 231-733-8870 x

MUSKEGON HEIGHTS, MI 49444

2724 Peck Street

2724 Peck Street

tbell@muskegonheights.us

tbell@muskegonheights.us

OP Mr. DAVE BONFOY

MUSKEGON HEIGHTS

DISTRIBUTION FOREMAN

MUSKEGON HEIGHTS, MI 49444

AC-Administrative; OW-Owner; DO-Operator in Charge; DS-Distribution Operator; OP-Operator, FC-Financial; PM-Property Manager; EC-Emergency; LE-Lead Engineer; SA-Sampler; LC-Legal; OT-Other; CC-Carbon Copy

Deficiency	Severity	Date Determined	Date Resolved	Comments	Description
MRAN Analytical Capabilities	MIN	3/30/2022		DUE: May 31, 2022	POE chlorine analyzer offline, repaired but now SCADA scale is not accurate. Turbidimeter calibration method not approved, no records of 2022 calibrations.

DSXC Cross Connections	MIN	3/30/2022	DUE: Implementation plan	Need to implement residential
			6/30/22, updates on progress 3/31/23, 3/31/24	program
FWCM Construction & Maintenance	MIN	3/30/2022	DUE: (5/25/2022, Corrective action plan in survey response letter)	24 mesh needed on overflow and method to verify free flowing
FWCM Construction & Maintenance	MIN	3/30/2022	DUE; (5/25/2022, corrective action plan needs to be in survey response letter)	24 mesh on overflow, flapper valve needs to be shut, verify valve position periodically, needs to conform to ten states standards (currently has direct connection to sanitary sewer)
FWCM Construction & Maintenance	MIN	3/30/2022	DUE: (5/25/2022, need corrective action plan in survey response letter)	Remove extended venting from rooftop wet interior access hatch, verify overflow pipe flapper valve and mesh condition
SMRS Reliability Study	MIN	3/30/2022	DUE: 10/31/22	Need to update or request waiver
SMOP Operations Oversight	MIN	3/30/2022	DUE: May 25, 2022 (survey response letter)	Not meeting distribution system oversight requirements (daily site visits, supervise staff directly) by OIC. Need to explain how City will satisfy requirements.
SERP Emergency Response Plan	MIN	3/30/2022	DUE: 7/31/2022	ERP needs to reflect rule requirements
FIBG Budget & Capital Improvement Plan	MIN	3/30/2022	DUE: 10/31/22	Need to update AMP to meet requirements, include rate study and CIP.

Туре	Violation Name	Code	Analyte Name	Period End	Period Begin	RTC Date
27	MONITORING, ROUTINE (DBP), MAJOR	2920	CARBON, TOTAL	1/1/2021	3/31/2021	2/17/202
ЗА	MONITORING, ROUTINE, MINOR (RTCR)	3014	E. COLI	10/1/2021	10/31/2021	11/8/202
S3	STATE M/R (ENTRY POINT CHEM/RAD)	1040	NITRATE	1/1/2012	9/30/2012	2/6/2013

Storage Facilities

Site Code ST100 Facility Name: WTP UNDERGROUND STORAGE Local Name: 4.5 MG

Type: UN Material: CC Coating: Status: A Constructed Date: 1/1/2000

Comments:

Indicato	r Type	Value and/or Date	Comments / Corrections / Updates
ALTV	Altitude Valve Indicator	NA	
COAD	Covered Indicator	YES 1/1/1753	
PRES	Pressurized Indicator	NO	
CAPR	Cathodic Protection	NO	
MXSY	Mixing System	NO	
DTIN	Date Last Inspected	5/12/2006	
ISVL	Isolation Valve	YES	
DRAI	Drain Present	YES	
MUDV	Mud Valve	NA	
Measure	Туро	Quantity / Units	
OFEL	Overflow Elevation	656.5 FT	
Flow Ra	to Typo	Quantity / Units	
APCD A	pproved Design Capacity	4500000 GAL	

Site Code ST200 Facility Name: SHERMAN RESERVOIRS Local Name: 1.5 MG

Type: RS Material: CC Coating: Status: A Constructed Date: 1/1/1940

Comments:

indicat	or Type	Value and/	or Date	Comments / Corrections / Updates
ALTV	Altitude Valve Indicator	NO		
COVD	Covered Indicator	YES	1/1/1753	
PRES	Pressurized Indicator	YES		
EMER	Emergency Power	NO		
CAPR	Cathodic Protection	NA		
MXSY	Mixing System	NO		
DTIN	Date Last Inspected	1.	1/10/2008	
ISVL	Isolation Valve	YES		
DRAI	Drain Present	NO		
MUDV	Mud Valve	NA		
Measur	е Туре	Quantity	/ Units	
OFEL	Overflow Elevation	12	IN	
THED	Total Head Elevation	5	FT	
NLWE	Normal Low Water Elevation/Pressure (pump cut-in)	7	FT	
Flow Re	te Type	Quantity:	/ Unite	
APCD A	Approved Design Capacity	1500000	GAL	

Monday, April 25, 2022 Page 1 of 4

Site Code ST300 Facility Name: GETTY STREET ELEVATED TANK Local Name: 750,000 GALLONS

Type: EL Material: ST Coating: ER Status: A Constructed Date: 1/1/1964

Comments:

Indicate	or Type	Value and	for Date	Comments / Corrections / Update
ALTV	Altitude Valve Indicator	YES	1/1/1753	
COVD	Covered Indicator	YES	1/1/1753	
PRES	Pressurized Indicator	YES	1/1/1753	
EMER	Emergency Power	YES	1/1/1753	
CAPR	Cathodic Protection	YES		
MXSY	Mixing System	NO		
DTIN	Date Last Inspected	I'	1/12/2018	
ISVL	Isolation Valve	YES		
DRAI	Drain Present	YES		
MUDV	Mud Valve	NO		
TABG	Tank Above Grade	YES		
Measun	Type	Quantity	/ Links	
OFEL	Overflow Elevation	767	FT	
NLWE	Normal Low Water Elevation/Pressure (pump cut-in)	754	FT	
NHWE	Normal High Water Elevation/Pressure (pump cut-out)	766	FT	
Flow Ra	ite Type	Quantity	/ Units	
APCD A	Approved Design Capacity	750000	GAL	

Type: EL=elevated GR=ground HD=hydropneumatic BL=bladder ST=standpipe UN=underground
Material: ST=steel CC=concrete AC=asbestos cement AS=asphalt CP=copper ER=earth FG=fiberglass PL=plastic WD=wood
Coating: AP=approved paint ER=epoxy resin FG=fiberglass GR=greased GS=glass-lined steel PL=plastic UN=unlined

Monday, April 25, 2022
Page 2 of 4

MI0004580 MUSKEGON HEI	GHTS	新文化是《民族教》 。21
Pump Facilities		
l	LOW SERVICE PUMP STATION Availability P Constructed:	Local Name: Modified:
1-	Value and/or Date YES YES YES Quantity / Units 33.9 MGD 10 MGD 25.3 MGD HIGH SERVICE PUMP STATION Availability P Constructed:	Comments / Corrections / Updates Local Name: WTP HIGH SERVICE STATIO Modified:
Pump Description:		
Indicator Type EMER Emergency Power METR Metered Flow Rate Type APCD Approved Design Capacity EMCP Capacity Under Emergency Pow FIRM Firm Capacity	35.48 MGD	Comments / Corrections / Updates
	SHERMAN PUMP STATION Availability P Constructed:	Local Name: Modified:
indicator Type EMER Emergency Power	Value and/or Date NO	Comments / Corrections / Updates

	THE PERSON NAMED IN COLUMN TWO IS NOT THE OWNER.	falue and/o	or Cate	Comments / Corrections / Updates
rgency Power		NO		
•		Quantity	Units	
ed Design Cap	pacity	15.2	MGD	
pacity		9.2	MGD	
trifugal JT=jet	PD=positive displacement	SC=screw	SU=submersible	VT=vertical turbine
a	ed Design Cap	ergency Power od Design Capacity apacity	ergency Power NO Quantity and Design Capacity 15.2 apacity 9.2	ergency Power NO Quantity / Units red Design Capacity 15.2 MGD

Monday, April 25, 2022 Page 3 of 4

Distribution System

Site Code DIST

Facility Name: DISTRIBUTION SYSTEM

Status: A

Comments:

Comments / Corrections / Updates

Intake Facilities

Site Code IN001 Facility Name: DUAL INTAKES 42 INCH

Local Name DIA 42 IN; LGT 4800 FT; SUB 45 FT

Water Body: LAKE MICHIGAN

Comments:

Status: A Availability P

Constructed: 1/1/2001 Modified:

Latitude: 43.18059 Longitude: -86.326

Comments / Corrections / Updates

Flow Rate Type

Quantity / Units

APCD Approved Design Capacity

34 MGD

Site Code IN225

Facility Name: LAKE MICHIGAN INTAKE 30 INCH

Local Name DIA 30 IN; LGT 4700 FT; SUB 38 FT

Water Body: LAKE MICHIGAN

Comments:

Status: A Availability P

Constructed: 1/1/1940 Modified:

Latitude: 43.18189 Longitude: -86.3272

Comments / Corrections / Updates

Plow Rate Type

Quantity / Units

APCD Approved Design Capacity

16 MGD

Treatment Facilities

Site Code: TP100 Facility Name: TREATMENT PLANT Status/Date: A 8/17/1941

Availability: P Constructed Date: Lat / Long: 43.18702 -86.30045

Local Name: MUSKEGON HEIGHTS WATER TREATMENT PLANT

Comments / Corrections / Updates

Treatment Process and Objective Pairings

FLUORIDATION OTHER

SEDIMENTATION PARTICULATE REMOVAL
RAPID MIX PARTICULATE REMOVAL
FLOCCULATION PARTICULATE REMOVAL

FILTRATION, RAPID SAND PARTICULATE REMOVAL
COAGULATION PARTICULATE REMOVAL

HYPOCHLORINATION, PRE DISINFECTION

Indicator Type Value and/or Date

 EMER
 Emergency Power
 YES

 EMPT
 Emergency Power Type
 PERM

 METR
 Metered
 YES

Flow Rate Type

APCD Approved Design Capacity

25.2 MGD

EMCP Capacity Under Emergency Power

10 MGD

Monday, April 25, 2022

Page 1 of 1